



materials:	
steel	\$800
concrete	\$200
-	
labor:	
welding fab	\$800
instalation	\$200
-	
total:	\$2000

9th st Bmx tool storage cage with large door  
 cage dimensions 5'X3' 7" tall  
 materials:  
 1.5" square tubing 1/8" wall  
 4" hog panel mesh galvanized  
 4"X4" 1/4" mounting plates  
 3/8" galvanized Wedge Type Expansion Anchors  
 5'x7' 4" thick, 4000 psi concrete pad  
 all metal coated with rust preventing paint



RECEPTION ↗

